DISTRICT BOARD, TUMKUR.

Notification No. C. 346—30-31, *dated 6th April* 1931.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Tumkur, up to 2 P.M., on the 30th April 1931, for constructing a native kitchen attached to Midigesi Travellers' Bungalow, Madhugiri Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed before the .....

2. The plan and the detailed estimate may be seen at the Office of the President, District Board, between the hours of 11 A.M. and 5 P.M., except on Sundays and authroised Public Holidays.

3. Tenders should be submitted on typed forms which may be obtained from the Office of the President. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 100 (one hundred only) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a native kitchen attached to the 3rd Class Travellers' Bungalow, at Midigesi", in default of which tenders will be rejected.

5. The final acceptance of the tender will rest with the President, District Board, Tumkur, who does not bind himself to accept the lowest or any tender or to asign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be written legibly both in figures and words without correction.

10. The contractor will not be allowed to claim enhanced rates after the submission of the tender at any stage.

11. The decision of the President, District Board, will be final and legally binding on the contractor in case of disputes about the rates, qualities and quantities of work.

ABSTRACT OF THE ESTIMATE.

Serial No.	Items of Work	Quantity	Per	Rate
1	Earthwork, excavation and filling basement	16	C.yds	
2	Burnt stone in mud filling fomdation and basement	567	C.ft.	
3	Burnt brick in clay—superstructure	821	,,	
4	Burnt brick in chunam—arch work	10	,,	
5	Burnt brick in chunam—sides of doors and windows	197	,,	
6	Burnt stone slabs dressed	118	S.ft	
7	Plastering with chunam	19.65	,,	
8	Whitewashing—two coats	19.65	,,	
9	Painting with chunam	1.27	,,	
10	Providing mortar and pestle stand	L. S.	L.S.	
11	Teak-wood wrought and put up with wood oiling	37.70	C.ft.	
12	Roofing with 1st class Tumkur tiles Mangalore pattern on teak reepers, the eave tiles being tied up by a teak batten screwed down to rafters.	7.40	Sqr.	
13	Ridge tiles set in mortar and cement pointing	29	R.ft.	
14	Ventilating tiles	4	each	
15	Teak-wood battened doors with iron work and chocolate painting, etc. complete	101	S.ft.	
16	Teak-wood windows battened shutters, iron bars, iron work and chocolate painting, etc., Complete	9	S.ft.	
17	Teak-wood glazed ventilators with iron bars, iron work and chocolate painting, etc., complete	22	S.ft.	
18	Flooring with 1st class Mangalore tiles over 3" concrete bed and cement pointing	2.73	Sqr.	
19	Binding walls over gable	42	R.ft.	
20	Constructing cistern wall with cement plastering and providing a galvanized iron pipe 2' long	L. S.	L.S.	
21	Teak-wood cave board ornamental including painting	110	R.ft.	
22	Clearing site, tarring wood work and levelling ground alround.	L. S.	L.S.	

D. S. MALLAPPA,
President, District Board,

3-3 F